

APPENDIX F

Third Quarter 2009 IML Calibration and Quality Assurance Audit Report



**Energy Fuels Resources Corporation
Piñon Ridge Mill**

**Calibration and Quality Assurance Audit Report for
Meteorological and Ambient Air Monitoring Network**

3rd Quarter 2009

Prepared by:



IML Air Science

a division of Inter-Mountain Laboratories, Inc.

555 Absaraka

Sheridan, Wyoming 82801

(307) 674-7506

www.imlairscience.com

1 Introduction

Inter-Mountain Laboratories – Air Science Division performed calibrations and quality assurance audits on July 15, 2009. The calibrations and audits included all (5) of the ambient air monitoring systems and the (2) meteorological monitoring systems at the Piñon Ridge Mill Site located approximately 15 miles from Naturita, Colorado. The Piñon Ridge Mill Site is operated by Energy Fuels Resources Corporation. This is a list of the monitoring sites and the associated equipment:

Site 1

- Meteorological Station – 10m Tower
 - Wind Speed
 - Wind Direction
 - Vertical Wind Speed
 - Temperature (2m & 10m)
 - Delta Temperature
 - Relative Humidity
 - Solar Radiation
 - Barometric Pressure
 - Precipitation
 - Evaporation
- PM₁₀ Sampler – Thermo FRM 2000 PM₁₀
- TSP Sampler – Tisch Hi-Vol 5170

Site 2

- Meteorological Station – 30m Tower
 - Wind Speed
 - Wind Direction
 - Vertical Wind Speed
 - Temperature (2m & 30m)
 - Delta Temperature
 - Relative Humidity
 - Solar Radiation
 - Barometric Pressure
- PM₁₀ Sampler – Thermo FRM 2000 PM₁₀
- TSP Sampler – Tisch Hi-Vol 5170

Site 3

- TSP Sampler – Tisch Hi-Vol 5170

Site 4

- TSP Sampler – Tisch Hi-Vol 5170

Site 5

- TSP Sampler – Tisch Hi-Vol 5170

1.1 Calibration and Audit References

The calibrations and audits were conducted in accordance with the following guideline documents:

- Ambient Monitoring Guidelines for the Prevention of Significant Deterioration (PSD), May 1987
- Environmental Protection Agency (EPA) Meteorological Monitoring Guidance for Regulatory Modeling Applications, February 2000 (MMGRMA) (EPA-454/R-99-005)
- Quality Assurance Handbook for Air Pollution Measurements Systems, Vol. I – A Field Guide to Environmental Quality Assurance, April 1994
- Quality Assurance Handbook for Air Pollution Measurements Systems, Vol. II – Ambient Air Quality Monitoring Program, December 2008
- Quality Assurance Handbook for Air Pollution Measurements Systems, Vol. IV – Meteorological Measurements, September 1989
- Quality Assurance Handbook for Air Pollution Measurement Systems, Vol. V, Meteorological Measurements, EPA 1995
- Ambient Air Monitoring Requirements for the Air Pollution Control Division of the Colorado Department of Public Health and Environment, Technical Services Program Air Pollution Control Division, April 2001
- U.S. Nuclear Regulatory Commission Regulatory Guide, Office of Standards Development, Regulatory Guide 4.14 – Radiological Effluent and Environmental Monitoring at Uranium Mills, Revision 1, April 1980
- U.S. Nuclear Regulatory Commission Regulatory Guide, Office of Nuclear Regulatory Research, Regulatory Guide 3.63 – Onsite Meteorological Measurement Program For Uranium Recovery Facilities – Data Acquisition and Reporting, March 1988.

2 Calibration and Audit Methodology and Accuracy Goals

2.1 Meteorological Stations

2.1.1 Wind Speed

The wind speed was verified by rotating the sensor shaft using a DC-powered variable-speed motor equipped with an optical encoder output referenced to a crystal oscillator. A standard sensor speed was calculated based on the audit rotational speed and compared to the instantaneous logger reading. An R.M. Young Torque Disc was used to ensure bearing integrity of the wind speed sensor. All data were recorded on a standardized audit form.

2.1.2 Wind Direction

The wind direction sensor orientation was verified by using a Brunton precision magnetic compass. Instantaneous direction readings from the logger were compared to the standards and recorded on a standardized form.

2.1.3 Temperature

Proper operation of the temperature sensors was verified by placing the sensors and a precision NIST-traceable electronic thermometer in three equilibrated temperature baths (ice bath, warm bath, and ambient bath). Both reference thermometer and logger readings were recorded on a standardized form.

2.1.4 Delta Temperature

Proper operation of the temperature sensors was verified by placing the sensors and a precision NIST-traceable electronic thermometer in three equilibrated temperature baths (ice bath, warm bath, and ambient bath). Both reference thermometer and logger readings were recorded on a standardized form.

2.1.5 Relative Humidity

The relative humidity was checked by co-locating a reference sensor next to the station sensor. The reading was taken and the difference between the calibration standard and the on-site data logger were compared to acceptance criteria.

2.1.6 Solar Radiation

The solar radiation was checked by co-locating a reference sensor next to the station sensor. The readings of covered and uncovered were taken and the differences between the calibration standard and the on-site data logger were compared to acceptance criteria.

2.1.7 Barometric Pressure

The barometric pressure was checked by co-locating a reference sensor next to the station sensor. The reading was taken and the difference between the calibration standard and the on-site data logger were compared to acceptance criteria.

2.1.8 Precipitation

The precipitation gauge was challenged three times using a lab quality burette and water. The volume of water required to cause the tipping bucket to activate was measured and volumes were recorded along with the calculated value for activation on a standardized form.

2.1.9 Evaporation

The evaporation pan was calibrated by using five points to calculate the resulting slope and intercept for the sensor. The calibration is completed by adding water to the evaporation pan and recording the values from a yardstick and the logger.

2.2 Ambient Air Monitoring

2.2.1 PM₁₀ FRM Partisol Samplers

The PM₁₀ FRM Partisol Sampler audits included a verification of the flow, barometric pressure, ambient temperature, and filter temperature. The flow audit was completed by removing the inlet of the sampler and installing a Flow Transfer Standard (FTS) with an associated digital manometer. The calculated flow of the FTS and the sampler flow were compared to the acceptance criteria.

Proper operation of the temperature sensors (ambient and filter) in the sampler were verified by comparing the sensors and a precision NIST-traceable electronic thermometer. Both reference thermometer and sampler readings were recorded on a standardized form.

The barometric pressure was checked by co-locating a reference sensor next to the sampler. The reading was taken and the difference between the audit standard and the sampler was compared to acceptance criteria.

2.2.2 TSP Hi-Volume Samplers

Audits of the Hi-Volume Samplers were completed by finding the numerical relationship between the sampler output (volumetric flow rate) and its flow indicator (stagnation pressure ratio). The stagnation pressure is an area of low pressure underneath the filter caused by the resistance to airflow through the filter. The stagnation pressure ratio is a mathematical relationship of stagnation and ambient pressures. To find the numerical relationship to the multiple point (multi-point) calibration was completed on the sampler. The audit flow and design flow are compared to the acceptable criteria. The following equipment was required for the audit:

- 1) National Institute of Standards and Technology (NIST) traceable variable resistance transfer standard (calibration orifice) with faceplate.
- 2) Portable thermometer, capable of accurately measuring temperature over the range of 0 to 50 °C to the nearest ± 1 °C and referenced to a NIST or American Society for Testing and Materials (ASTM) thermometer within ± 2 °C at least annually.
- 3) Portable barometer, capable of accurately measuring ambient barometric pressure over the range of 500 to 800 millimeters of mercury (mm Hg) to the nearest millimeter of mercury, and referenced within ± 5 mm Hg to a barometer of known accuracy at least annually.
- 4) Digital manometers (0 – 20" and 0 – 40") with tubing.

2.3 Calibration Thresholds

Calibration goals for the parameters measured by the meteorological monitoring system are those specified in the US EPA *Quality Assurance Handbook for Air Pollution Measurement Systems, Volume IV, Meteorological Measurements*, March 1995. Accuracy goals by parameter are shown below.

Table 2-1 – Meteorological Sensor Criteria

Sensor	Specifications
Wind Speed	±0.5 m/s
Wind Speed – Starting Threshold	< 0.5 gm-cm
Wind Direction	± 5.0 compass degrees
Vertical Wind Speed	±.2 m/s ± 5.0 percent of observed
Temperature	±0.5 °C
Delta Temperature	±0.1 °C
Relative Humidity	±5.0 %
Solar Radiation	±5.0 percent of observed
Barometric Pressure	±0.09 in Hg
Precipitation	±10 percent of observed

2.4 Audit Thresholds

Audit goals for the parameters measured by the meteorological monitoring system are those specified in the US EPA *Quality Assurance Handbook for Air Pollution Measurement Systems, Volume II, Ambient Air Quality Monitoring Program*, December 2008. Accuracy goals by parameter are shown below.

Table 2-2 – PM₁₀ Sampler Criteria

Sensor	Specifications
Ambient Temperature	±2.0 °C
Filter Temperature	±2.0 °C
Pressure	± 10 mm Hg
Flow Rate	±4.0 percent of observed (±0.67 lpm)
External Leak Check	<5.0 in Hg / 60 seconds
Internal Leak Check	<8.5 in Hg / 30 seconds

Table 2-3 – TSP Sampler Criteria

Sensor	Specifications
Audit Flow Difference	±6.0 percent
Design Flow Difference	±7.0 percent

3 Calibration and Audit Results

Calibration and Audit results for Site #1 – 5 can be found in Appendices A, B, and C.

4 Findings/Recommendations

The calibrations and audit of the Ambient Air Monitoring equipment were within the specifications during the 3rd Quarter of 2009. The calibrations of the Meteorological Monitoring equipment were within the calibration specifications at Site #1 and Site #2, including the evaporation pan. The quality assurance audits on the equipment at the Site #1, #2, #3, #4, and #5 were all within specifications. Results of the calibration and audits can be found in Appendix A, B, and C.

Appendix A

PM₁₀ Sampler Audits



Partisol FRM Single Point Audit

Network: Energy Fuels
Date: 7/15/2009
Time: 0743 MST
Audited by: W. Adler
Streamline FTS ID: 081002
Streamline FTS cal. expires: 11/18/2009
Streamline FTS "m": 0.4342
Streamline FTS "b": -0.4678
Temp Standard ID: IML 0987
Press Standard ID: IML 0913
Manometer ID: IML 0983
Notes as found: Ok

Sampler ID: 1-2

As-Found Calibration Values

Parameter	Offset	Span
A/I	-0.0003	0.9993
Amb. Temp.	0.0072	
Filter Temp.	0.0066	
Pressure	-0.0363	
Flow	-0.0058	0.9656

Sensors Audit

Sensor	Indicated	ΔP	Actual	Difference	Specification
Amb. Temp.	25.5		25.4	0.1	$\pm 2^{\circ}\text{C}$
Filter Temp.	25.4		25.3	0.1	$\pm 2^{\circ}\text{C}$
Pressure	627.0		629.2	2.2	$\pm 10 \text{ mmHg}$
Flow	16.70	4.34	16.71	0.01	16.7 lpm $\pm 4\%$ ($\pm 0.67 \text{ lpm}$)

External Leak Check: Pass
 (<8.5"Hg/30 sec.)

Internal Leak Check: Pass
 (<8.5"Hg/30 sec.)

Notes:



Partisol FRM Single Point Audit

Network: Energy Fuels
Date: 7/15/2009
Time: 1022 MST
Audited by: R. Campbell
Streamline FTS ID: 081001
Streamline FTS cal. expires: 11/18/2009
Streamline FTS "m": 0.4413
Streamline FTS "b": -0.4728
Temp Standard ID: IML 0987
Press Standard ID: IML 0913
Manometer ID: IML 0983
Notes as found: Ok

Sampler ID: 2-2

As-Found Calibration Values

Parameter	Offset	Span
A/I	-0.0020	0.9996
Amb. Temp.	-0.0003	
Filter Temp.	-0.0032	
Pressure	-0.0075	
Flow	-0.0115	0.9898

Sensors Audit

Sensor	Indicated	ΔP	Actual	Difference	Specification
Amb. Temp.	29.5		30.4	0.9	$\pm 2^{\circ}\text{C}$
Filter Temp.	30.7		31.7	1.0	$\pm 2^{\circ}\text{C}$
Pressure	624.0		627.4	3.4	$\pm 10 \text{ mmHg}$
Flow	16.60	4.07	16.62	0.02	16.7 lpm $\pm 4\%$ ($\pm 0.67 \text{ lpm}$)

External Leak Check: Pass
 (<8.5"Hg/30 sec.)

Internal Leak Check: Pass
 (<8.5"Hg/30 sec.)

Notes:

Appendix B

TSP Sampler Audits

Sampler Flow Rate Audit

Network: Energy Fuels Resources

Sampler ID: 1-1

Sampler Type: Tisch TE-5170-DV-BL

AIRS Site ID:

Audited By: W. Adler

Sampler Audit Date: 7/15/2009

Sampler Calibration Date: 7/14/2009

Orifice ID: B

Orifice Calibration Date: 3/3/2009

Ambient Temperature (°C): 38.9

Ambient Pressure ("Hg): 24.71

Ambient Temperature (°K): 312.1

Ambient Pressure (mmHg): 628

Orifice Calibration: $Q_a = \{\text{SQRT} [\Delta P * (T_a / P_a)] - b\} * \{1/m\}$

where $m = 1.268$ and $b = -0.024$

Sampler Calibration: $Q_a = \{[P1/P_a - b]*[\text{SQRT}(T_a)]\} * \{1/m\}$

where $m = 11.0731$ and $b = 0.1550$

Accuracy Flow Audit

ΔP ("H ₂ O)	Orifice	Q_a (m ³ /min)	ΔP ("H ₂ O)	Sampler	Q_a (m ³ /min)
4.62	⇒	1.2142	23.0	⇒	1.2388

Sampler Q_a percent difference from Orifice Q_a : 2.0%

Design Flow Audit

Sampler with Orifice Removed

ΔP ("H ₂ O)	Q_a (m ³ /min)
19.5	⇒ 1.2554

Corrected Sampler Q_a : 1.2303 m³/min

Design Q_a : 1.2000 m³/min

Corrected sampler Q_a percent difference from design Q_a : 2.5%

Audit performed according to EPA Quality Assurance Handbook for Air Pollution Measurement Systems: Volume II, Ambient Air Specific Methods.

Notes:

Sampler Flow Rate Audit

Network: Energy Fuels Resources

Sampler ID: 2-1

Sampler Type: Tisch TE-5170-DV-BL

AIRS Site ID:

Audited By: R. Campbell

Sampler Audit Date: 7/15/2009

Sampler Calibration Date: 7/15/2009

Orifice ID: B

Orifice Calibration Date: 3/3/2009

Ambient Temperature (°C): 35.3

Ambient Pressure ("Hg): 24.68

Ambient Temperature (°K): 308.5

Ambient Pressure (mmHg): 627

Orifice Calibration: $Q_a = \{\text{SQRT} [\Delta P * (T_a / P_a)] - b\} * \{1/m\}$

where $m = 1.268$ and $b = -0.024$

Sampler Calibration: $Q_a = \{[P1/P_a - b]*[\text{SQRT}(T_a)]\} * \{1/m\}$

where $m = 10.6371$ and $b = 0.2029$

Accuracy Flow Audit

Orifice		Sampler	
ΔP ("H ₂ O)	Qa (m ³ /min)	ΔP ("H ₂ O)	Qa (m ³ /min)
4.34	⇒ 1.1714	21.0	⇒ 1.2130

Sampler Qa percent difference from Orifice Qa: **3.6%**

Design Flow Audit

Sampler with Orifice Removed

ΔP ("H ₂ O)	Qa (m ³ /min)
17.6	⇒ 1.2297

Corrected Sampler Qa: 1.1854 m³/min

Design Qa: 1.2000 m³/min

Corrected sampler Qa percent difference from design Qa: **-1.2%**

Audit performed according to EPA Quality Assurance Handbook for Air Pollution Measurement Systems: Volume II, Ambient Air Specific Methods.

Notes:

Sampler Flow Rate Audit

Network: Energy Fuels Resources

Sampler ID: 3-1

Sampler Type: Tisch TE-5170-DV-BL

AIRS Site ID:

Audited By: R. Campbell

Sampler Audit Date: 7/15/2009

Sampler Calibration Date: 7/15/2009

Orifice ID: B

Orifice Calibration Date: 3/3/2009

Ambient Temperature (°C): 34.7

Ambient Pressure ("Hg): 24.65

Ambient Temperature (°K): 307.9

Ambient Pressure (mmHg): 626

Orifice Calibration: $Q_a = \{\text{SQRT} [\Delta P * (T_a / P_a)] - b\} * \{1/m\}$

where $m = 1.268$ and $b = -0.024$

Sampler Calibration: $Q_a = \{[P1/P_a - b]*[\text{SQRT}(T_a)]\} * \{1/m\}$

where $m = 9.8476$ and $b = 0.2471$

Accuracy Flow Audit

Orifice		Sampler	
ΔP ("H ₂ O)	Qa (m ³ /min)	ΔP ("H ₂ O)	Qa (m ³ /min)
4.46	⇒ 1.1868	22.1	⇒ 1.2242

Sampler Qa percent difference from Orifice Qa: **3.2%**

Design Flow Audit

Sampler with Orifice Removed

ΔP ("H ₂ O)	Qa (m ³ /min)
18.8	⇒ 1.2414

Corrected Sampler Qa: 1.2017 m³/min

Design Qa: 1.2000 m³/min

Corrected sampler Qa percent difference from design Qa: **0.1%**

Audit performed according to EPA Quality Assurance Handbook for Air Pollution Measurement Systems: Volume II, Ambient Air Specific Methods.

Notes:

Sampler Flow Rate Audit

Network: Energy Fuels Resources

Sampler ID: 4-1

Sampler Type: Tisch TE-5170-DV-BL

AIRS Site ID:

Audited By: W. Adler

Sampler Audit Date: 7/15/2009

Sampler Calibration Date: 7/15/2009

Orifice ID: B

Orifice Calibration Date: 3/3/2009

Ambient Temperature (°C): 37.3

Ambient Pressure ("Hg): 24.92

Ambient Temperature (°K): 310.5

Ambient Pressure (mmHg): 633

Orifice Calibration: $Q_a = \{\text{SQRT} [\Delta P * (T_a / P_a)] - b\} * \{1/m\}$

where $m = 1.268$ and $b = -0.024$

Sampler Calibration: $Q_a = \{[P1/P_a - b]*\text{SQRT}(T_a)\}*\{1/m\}$

where $m = 12.0757$ and $b = 0.0956$

Accuracy Flow Audit

ΔP ("H ₂ O)	Orifice	Q_a (m ³ /min)	ΔP ("H ₂ O)	Sampler	Q_a (m ³ /min)
4.65	⇒	1.2099	22.6	⇒	1.2224

Sampler Q_a percent difference from Orifice Q_a : 1.0%

Design Flow Audit

Sampler with Orifice Removed

ΔP ("H ₂ O)	Q_a (m ³ /min)
19.0	⇒ 1.2376

Corrected Sampler Q_a : 1.2252 m³/min

Design Q_a : 1.2000 m³/min

Corrected sampler Q_a percent difference from design Q_a : 2.1%

Audit performed according to EPA Quality Assurance Handbook for Air Pollution Measurement Systems: Volume II, Ambient Air Specific Methods.

Notes:

Sampler Flow Rate Audit

Network: Energy Fuels Resources

Sampler ID: 5-1

Sampler Type: Tisch TE-5170-DV-BL

AIRS Site ID:

Audited By: R. Campbell

Sampler Audit Date: 7/15/2009

Sampler Calibration Date: 7/15/2009

Orifice ID: B

Orifice Calibration Date: 3/3/2009

Ambient Temperature (°C): 33.5

Ambient Pressure ("Hg): 24.57

Ambient Temperature (°K): 306.7

Ambient Pressure (mmHg): 624

Orifice Calibration: $Q_a = \{\text{SQRT} [\Delta P * (T_a / P_a)] - b\} * \{1/m\}$

where $m = 1.268$ and $b = -0.024$

Sampler Calibration: $Q_a = \{[P1/P_a - b]*\text{SQRT}(T_a)\}*\{1/m\}$

where $m = 11.1194$ and $b = 0.1509$

Accuracy Flow Audit

Orifice		Sampler	
ΔP ("H ₂ O)	Qa (m ³ /min)	ΔP ("H ₂ O)	Qa (m ³ /min)
4.44	⇒ 1.1838	25.6	⇒ 1.2166

Sampler Qa percent difference from Orifice Qa: **2.8%**

Design Flow Audit

Sampler with Orifice Removed

ΔP ("H ₂ O)	Qa (m ³ /min)
22.3	⇒ 1.2321

Corrected Sampler Qa: 1.1976 m³/min

Design Qa: 1.2000 m³/min

Corrected sampler Qa percent difference from design Qa: **-0.2%**

Audit performed according to EPA Quality Assurance Handbook for Air Pollution Measurement Systems: Volume II, Ambient Air Specific Methods.

Notes:

Appendix C

Meteorological System Calibrations

METEOROLOGICAL STATION CALIBRATION SUMMARY

Met Station: Energy Fuels - Site #1 (10m Tower)

Calibration Date: 15-Jul-09

Calibration Performed By: R. Campbell, W. Adler - IML Air Science

Sensor	Mfr./Model	Serial Number	Reference Device	Serial/ID Number
Wind Speed 10m (WS):	RM Young Wind Monitor AQ	82346	quartz referenced drive motor	IML 0857
Wind Direction 10m (WD):	RM Young Wind Monitor AQ	82346	transit, compass	IML 0942
Temperature @ 2 Meters:	RM Young Platinum RTD Temp Probe	13638	digital thermistor	IML 1402
Temperature @ 10 Meters:	RM Young Platinum RTD Temp Probe	13639	digital thermistor	IML 1402
Relative Humidity (RH):	CSI CS 500	C2430074	digital hygrometer	IML 0890
Barometric Pressure (BP):	PTB 101B	C2430048	digital barometer	IML 1404
Solar Radiation:	LI-COR LI200SZ	PY57101	collocated LI200X	PY54289
Precipitation:	Met One 12" tipping bucket	G6356	lab grade burette	N/A
Data acquisition system:	CSI CR3000 datalogger	2397	N/A	N/A

Calibration Results

	Reference		DAS Value	Difference	Specification		
	RPM	m/s					
AQ WS 10 meters (cm/s)	0	0.00	0.00	0.00	below threshold		
	300	1.54	1.54	0.00	0.56	(2)	
	800	4.10	4.10	0.00	0.56	(2)	
	3000	15.36	15.36	0.00	0.77	(2)	
	8000	40.96	40.96	0.00	2.05	(2)	
WS 10 m start torque (gm-cm)		Reference	DAS Value	Difference	Specification		
		$\tau < 0.5$	N/A	N/A	1.0	(3)	
WD 10 meters (degrees)		0.0	0.1	0.1	5.0	(2)	
		90.0	90.1	0.1	5.0	(2)	
		180.0	180.3	0.3	5.0	(2)	
		270.0	270.2	0.2	5.0	(2)	
Vertical WS 10 meters (cm/s) (Clockwise)		Reference	Reference	DAS Value	Difference	Specification	
		RPM	cm/s				
		0	0.00	0.00	0.00	below threshold	
		200	100.00	98.10	1.90	25.00 (2)	
	EPS:	600	300.00	296.20	3.80	35.00 (2)	
		2000	1000.00	978.30	21.70	70.00 (2)	
		5000	2500.00	2431.50	68.50	145.00 (2)	
		0	0.00	0.00	0.00	below threshold	
		200	100.00	98.97	1.03	25.00 (2)	
	CFT:	600	300.00	301.60	1.60	35.00 (2)	
		2000	1000.00	986.70	13.30	70.00 (2)	
		5000	2500.00	2469.60	30.40	145.00 (2)	
	Vertical WS 10 meters (cm/s) (Counter-Clockwise)		0	0.00	0.00	0.00	below threshold
		200	-100.00	-98.40	1.60	25.00 (2)	
EPS:		600	-300.00	-301.00	1.00	35.00 (2)	
		2000	-1000.00	-975.30	24.70	70.00 (2)	
		5000	-2500.00	-2430.40	69.60	145.00 (2)	
		0	0.00	0.00	0.00	below threshold	
		200	-100.00	-100.45	0.45	25.00 (2)	
CFT:		600	-300.00	-296.03	3.97	35.00 (2)	
		2000	-1000.00	-992.69	7.31	70.00 (2)	
		5000	-2500.00	-2478.20	21.80	145.00 (2)	
WS 10 m start torque (gm-cm)			$\tau < 0.5$	N/A	N/A	1.0	(3)

		Reference (°C):	DAS Value	Difference	Specification	
Temp. (°C): 2 meter		0.50	0.51	0.01	0.5	(2)
		21.32	21.29	0.03	0.5	(2)
		51.02	50.98	0.04	0.5	(2)
Temp. (°C): 10 meter		0.50	0.51	0.01	0.5	(2)
		21.32	21.30	0.02	0.5	(2)
		51.02	51.00	0.02	0.5	(2)
		Reference	DAS Value	Difference	Specification	
Relative Humidity (%)		27.5	25.7	1.8	5.0	(2)
RH Sensor Temp (°C):		67.0	66.8	0.2		
Solar Radiation (W/m ²)	un-covered	162.88	157	5.7	8.1	(4)
	covered	0.21	0.07			
Barometric Pressure ("Hg)		24.75	24.74	0.01	0.09	(4)
		DAS Value (in)	Reference (ml)	DAS Equivalent	Difference	Specification
Precipitation (0.1" equiv.)		0.10	187.8	185.3	2.5	18.5 (2)
		0.10	184.0	185.3	1.3	18.5 (2)
		0.10	185.2	185.3	0.1	18.5 (2)
				Average Diff:	1.3	18.5 (2)
		2m sensor	10m sensor	ΔT - B	Specification	
Delta Temperature (°C):		0.51	0.51	0.00	0.1	(2)
		21.29	21.30	0.01	0.1	(2)
		50.98	51.00	0.02	0.1	(2)
BOLD difference values exceed performance specifications						
(1)= Performance specification listed in facilities' Quality Assurance Project Plan						
(2)= EPA Quality Assurance Manual for Air Pollution Measurement Systems, Vol. IV, 1989						
(3)= Manufacturer's Specifications						
(4)= EPA On-Site Meteorological Program Guidance for Regulatory Modeling Applications						
Notes, Recommendations						
System offline at 0610 MST and returned online at 0742 MST.						

METEOROLOGICAL STATION CALIBRATION SUMMARY

Met Station: Energy Fuels - Site #2 (30m Tower)

Calibration Date: 15-Jul-09

Calibration Performed By: R. Campbell, W. Adler - IML Air Science

Sensor	Mfr./Model	Serial Number	Reference Device	Serial/ID Number
Wind Speed 30m (WS):	RM Young Wind Monitor AQ	82347	quartz referenced drive motor	IML 0857
Wind Direction 30m (WD):	RM Young Wind Monitor AQ	82347	transit, compass	IML 0942
Temperature @ 2 Meters:	RM Young Platinum RTD Temp Probe	13640	digital thermistor	IML 1402
Temperature @ 30 Meters:	RM Young Platinum RTD Temp Probe	13641	digital thermistor	IML 1402
Relative Humidity (RH):	CSI CS 500	C2730148	digital hygrometer	IML 0890
Barometric Pressure (BP):	PTB 101B	C2750056	digital barometer	IML 1404
Solar Radiation:	LI-COR LI200SZ	PY57102	collocated LI200X	PY54289
Data acquisition system:	CSI CR3000 datalogger	2421	N/A	N/A

Calibration Results

	Reference		DAS Value	Difference	Specification		
	RPM	m/s					
AQ WS 30 meters (cm/s)	0	0.00	0.00	0.00	below threshold		
	300	1.54	1.54	0.00	0.56	(2)	
	800	4.10	4.10	0.00	0.56	(2)	
	3000	15.36	15.36	0.00	0.77	(2)	
	8000	40.96	40.96	0.00	2.05	(2)	
WS 30 m start torque (gm-cm)	Reference		DAS Value	Difference	Specification		
	$\tau < 0.5$		N/A	N/A	1.0	(3)	
WD 30 meters (degrees)	Reference		DAS Value	Difference	Specification		
	0.0		0.6	0.6	5.0	(2)	
	90.0		90.0	0.0	5.0	(2)	
	180.0		179.8	0.2	5.0	(2)	
		270.0	270.7	0.7	5.0	(2)	
Vertical WS 30 meters (cm/s) (Clockwise)	Reference		Reference	DAS Value	Difference	Specification	
	RPM		cm/s				
	0		0.00	0.00	0.00	below threshold	
	200		100.00	100.20	0.20	25.00 (2)	
	EPS:	600		300.00	298.10	1.90	35.00 (2)
		2000		1000.00	966.50	33.50	70.00 (2)
		5000		2500.00	2415.00	85.00	145.00 (2)
	0		0.00	0.00	0.00	below threshold	
	200		100.00	100.70	0.70	25.00 (2)	
	CFT:	600		300.00	297.90	2.10	35.00 (2)
		2000		1000.00	981.60	18.40	70.00 (2)
		5000		2500.00	2455.00	45.00	145.00 (2)
	Vertical WS 30 meters (cm/s) (Counter-Clockwise)	Reference		Reference	DAS Value	Difference	Specification
RPM		cm/s					
0		0.00	0.00	0.00	below threshold		
200		-100.00	-98.30	1.70	25.00 (2)		
EPS:		600		-300.00	-291.10	8.90	35.00 (2)
		2000		-1000.00	-966.40	33.60	70.00 (2)
		5000		-2500.00	-2411.00	89.00	145.00 (2)
0		0.00	0.00	0.00	below threshold		
200		-100.00	-99.30	0.70	25.00 (2)		
CFT:		600		-300.00	-296.10	3.90	35.00 (2)
		2000		-1000.00	-982.50	17.50	70.00 (2)
		5000		-2500.00	-2464.00	36.00	145.00 (2)
WS 30 m start torque (gm-cm)		$\tau < 0.5$		N/A	N/A	1.0	(3)

		Reference (°C):	DAS Value	Difference	Specification	
Temp. (°C): 2 meter		8.05	8.12	0.07	0.5	(2)
		25.05	25.01	0.04	0.5	(2)
		38.32	38.24	0.08	0.5	(2)
Temp. (°C): 30 meter		8.05	8.19	0.14	0.5	(2)
		25.05	25.02	0.03	0.5	(2)
		38.32	38.24	0.08	0.5	(2)
		Reference	DAS Value	Difference	Specification	
Relative Humidity (%)		11.4	10.9	0.5	5.0	(2)
RH Sensor Temp (°C):		92.5	93.1	0.6		
Solar Radiation (W/m ²)	un-covered	1112	1059.00	53.0	55.6	(4)
	covered	0.63	1.45			
Barometric Pressure ("Hg)		24.65	24.70	0.05	0.09	(4)
		2m sensor	10m sensor	ΔT - B	Specification	
Delta Temperature (°C):		8.12	8.19	0.07	0.1	(2)
		25.01	25.02	0.01	0.1	(2)
		38.24	38.24	0.00	0.1	(2)
BOLD difference values exceed performance specifications						
(1)= Performance specification listed in facilities' Quality Assurance Project Plan						
(2)= EPA Quality Assurance Manual for Air Pollution Measurement Systems, Vol. IV, 1989						
(3)= Manufacturer's Specifications						
(4)= EPA On-Site Meteorological Program Guidance for Regulatory Modeling Applications						
Notes, Recommendations						
System offline at 1020 MST and returned online at 1247 MST						

Evaporation Pan Verification Sheet

Evap Span **9.4612**
Evap Offset **1.5018**

Empty Pan Logger Reading:

Verification Point	Yardstick Reading (in)*	Logger Reading	Percent Difference
1	5.375	5.37200	-0.1%

Notes:

* Yard Stick Reading - taken at the pan outlet to the gauge

Offline: 0610 MST

Online: 0742 MST

Appendix D

Transfer Standard Certifications

Certificate of Accuracy

Transfer Standard Type: Barometric Pressure/Altimeter

Certificate No: B 042209. 02

Transfer standard model: Pretel AltiPlus A2
 Serial number: 13785 IML 0913
 submitted by/owner: Inter-Mountain Laboratories, Inc.
 Air Science Division
 555 Absaraka Street
 Sheridan, WY 82801

Was compared to Precision Absolute Reference Barometer:
 Model number: 355-AI0900 Serial number: 913930-M1
 Certified accuracy of ± 0.007 "Hg
 NIST traceable to Ruska Deadweight Tester SN 38342/C-85

Date: 04/22/09 Lab temperature 73.5 °F
 Lab pressure 668.9 mm Hg

Reference barometer ("Hg)	Transfer Standard ("Hg)	Difference from Reference ("Hg)	Transfer Standard Correction* ("Hg)
24.00	24.04	0.04	-0.04
25.00	25.03	0.03	-0.03
25.84	25.86	0.02	-0.02
27.50	27.52	0.02	-0.02
30.00	30.01	0.01	-0.01

Note:
 If no sign is given on the correction, the true pressure is higher than the indicated pressure. If the sign is negative, the true pressure is lower than the indicated pressure.

Transfer Standard adjustments made? YES NO

Post-calibration measurements:

Reference barometer ("Hg)	Transfer Standard ("Hg)	Difference from Reference ("Hg)	Transfer Standard Correction* ("Hg)

Reviewed:  Date: April 22, 2009

Roger L. Sanders, PE

Chinook Engineering
 a division of Inter-Mountain Laboratories, Inc.
 555 Absaraka Street
 Sheridan, Wyoming 82801 USA
 (307) 672-7790
 chinook@imlinc.com

Certificate of Accuracy

Transfer Standard Type: Barometric Pressure/Altimeter

Certificate No: B 091009. 02

Transfer standard model: Suunto Escape 203 Electronic Altimeter/Barometer

Serial number: 74605246 IML 1404

submitted by/owner: Inter-Mountain Laboratories, Inc.

Air Science Division

555 Absaraka Street

Sheridan, WY 82801

Was compared to Precision Absolute Reference Barometer:

Model number: 355-AI0900

Serial number: 913930-M1

Certified accuracy of ± 0.007 "Hg

NIST traceable to Ruska Deadweight Tester SN 38342/C-85

Date: 09/10/09

Lab temperature

75.7

°F

Lab pressure

663.2

mm Hg

Reference barometer ("Hg)	Transfer Standard ("Hg)	Difference from Reference ("Hg)	Transfer Standard Correction*
24.00	23.95	-0.05	0.05
25.00	24.95	-0.05	0.05
26.10	26.05	-0.05	0.05
26.50	26.45	-0.05	0.05
27.55	27.50	-0.05	0.05

Note:


If no sign is given on the correction, the true pressure is higher than the indicated pressure. If the sign is negative, the true pressure is lower than the indicated pressure.

Transfer Standard adjustments made? YES NO

Post-calibration measurements:

Reference barometer ("Hg)	Transfer Standard ("Hg)	Difference from Reference ("Hg)	Transfer Standard Correction*

Certified By:



Date: September 10, 2009

Roger L. Sanders, PE

Chinook Engineering

a division of Inter-Mountain Laboratories, Inc.

555 Absaraka Street

Sheridan, Wyoming 82801 USA

(307) 672-7790

chinook@imlinc.com

Certificate of Accuracy

Transfer Standard Type: Electronic Hygrometer

Certificate No: H 120208. 01

Transfer standard, model/type: Dwyer Series 485 Digital Hygrometer

Serial number: IML 0890

submitted by/owner: Inter-Mountain Laboratories, Inc.

Air Science Division

555 Absaraka Street

Sheridan, WY 82801

Was compared to Saturated Salt Solution Standards using ASTM Method E 104 - 02, Standard Practice for Maintaining Constant Relative Humidity by Means of Aqueous Solutions, using Temperature Reference Standard Streamline™ Pro MultiCal™ System Remote Temperature Probe S/N T030301.

Date: 11/30/2008 - 12/02/2008

Lab temperature: 68 - 72 °F


Barometric Pressure: 653.8 - 663.7 mmHG

Lab %RH: 35 - 45%

Reference Salt Standard	Reference Temperature °C	Reference Standard (%RH)	Uncertainty	Transfer Standard (%RH)	Difference from Reference (%RH)	Transfer Standard Correction* (%RH)
Lithium Chloride	20.3	11.82	±0.72	11.9	0.1	-0.1
Potassium Acetate						
Magnesium Chloride	19.6	33.09	±0.21	32.5	-0.6	0.6
Magnesium Nitrate	20.1	54.35	±0.23	52.3	-2.1	2.1
Sodium Chloride	19.6	75.48	±0.20	75.1	-0.4	0.4

Temperature Reference Standard (°C)	Transfer Standard (°C)	Difference from Reference (°C)	Transfer Standard Correction* (°C)
20.3	20.3	0.0	0.0
19.6	19.8	0.2	-0.2
20.1	19.9	-0.2	0.2
19.6	19.3	-0.3	0.3

Reviewed:



Date:

12/2/08

Roger L. Sanders, PE

Chinook Engineering

a division of Inter-Mountain Laboratories, Inc.

555 Absaraka Street

Sheridan, Wyoming 82801 USA

(307) 672-7790

chinook@imlinc.com

Certificate of Calibration

Streamline™ flow transfer standard (FTS) # 081001
 was calibrated against NIST traceable critical flow venturis
 S/Ns 10961, 10962, 10963, 18491, 30421 on: 11/18/2008

This calibration expires: **11/18/2009**

New

The actual flow rate (Q_a) through the FTS is:

$$Q_a = \left[m \times \left(\sqrt{\frac{(\Delta P)(T_{amb})}{P_{amb}}} \right) \right] + b$$

$m = 0.4413$

$b = -0.4728$

Q_a = actual flow rate in liters/minute

ΔP = pressure reading from the manometer in "H₂O

T_{amb} = ambient temperature in Kelvins

P_{amb} = ambient pressure in atmospheres*

* 1 atmosphere = 760 mmHg, = 29.92"Hg, =101,325 Pa

Reviewed: *RJA*

Date: *11/18/08*

Quality Assurance Check

Primary Standard Q_{actual} (l/min)	Streamline FTS ΔP ("H ₂ O)	Streamline FTS $Q_{line\ fit}$ (l/min)	Absolute Difference (l/min)	% Difference* full scale
20.02	6.35	20.04	0.02	0.10%
17.50	4.88	17.50	0.00	0.00%
14.99	3.60	14.97	-0.01	-0.07%
12.48	2.52	12.45	-0.02	-0.10%
9.98	1.65	9.98	0.00	0.00%
7.48	0.95	7.48	0.00	-0.01%
4.98	0.45	5.00	0.02	0.08%
T_a (°C)= 23.2				
P_a (atm)= 0.871		$r = 1.0000$		
*all points must be within ±2%				

Chinook Engineering

A Division of Inter-Mountain Laboratories, Inc.

555 Absaraka Street

Sheridan, Wyoming 82801 USA

(307) 672-7790

chinook@imlinc.com

Streamline™ FTS, US Patent #5792966

Certificate of Calibration

Streamline™ flow transfer standard (FTS) # 081002
 was calibrated against NIST traceable critical flow venturis
 S/Ns 10961, 10962, 10963, 18491, 30421 on: 11/18/2008

This calibration expires: **11/18/2009**

New

The actual flow rate (Q_a) through the FTS is:

$$Q_a = \left[m \times \left(\sqrt{\frac{(\Delta P)(T_{amb})}{(P_{amb})}} \right) \right] + b$$

$$m = 0.4342$$

$$b = -0.4678$$


Q_a = actual flow rate in liters/minute

ΔP = pressure reading from the manometer in "H₂O

T_{amb} = ambient temperature in Kelvins

P_{amb} = ambient pressure in atmospheres*

* 1 atmosphere = 760 mmHg, = 29.92"Hg, =101,325 Pa

Reviewed: 

Date: 11/18/08

Quality Assurance Check

Primary Standard Q_{actual} (l/min)	Streamline FTS ΔP ("H ₂ O)	Streamline FTS $Q_{line\ fit}$ (l/min)	Absolute Difference (l/min)	% Difference* full scale
20.01	6.55	20.04	0.03	0.14%
17.49	5.02	17.48	-0.01	-0.05%
14.99	3.72	14.98	-0.01	-0.03%
12.48	2.61	12.46	-0.02	-0.09%
9.98	1.70	9.96	-0.02	-0.08%
7.48	0.99	7.49	0.01	0.03%
4.99	0.47	5.01	0.02	0.10%

T_a (°C) = 23.3

P_a (atm) = 0.871

$r = 1.0000$

*all points must be within ±2%

Chinook Engineering

A Division of Inter-Mountain Laboratories, Inc.

555 Absaraka Street

Sheridan, Wyoming 82801 USA

(307) 672-7790

chinook@imlinc.com

Streamline™ FTS, US Patent #5792966

CERTIFICATE OF CALIBRATION

Orifice Transfer Standard - **B**

IML Air Science Sheridan, WY

B orifice transfer standard was calibrated on the NIST traceable
Dresser rootsmeter serial # 9217756 on 3-Mar-09

Calibration expires 3-Mar-10

The reference flow rate (Q_r) through the orifice, in cubic meters per minute, is:

$$Q_r = A (\Delta P_o)^B \quad r = 0.9997$$

where: $A = 0.510$

$B = 0.490$

ΔP_o = pressure drop across orifice, in inches of water

The actual flow rate (Q_a) through the orifice, in cubic meters per minute, is:

$$Q_a = \frac{\left[\left(\sqrt{(\Delta P_o) \left(\frac{T_a}{P_a} \right)} \right) - b \right]}{m} \quad r = 0.9998$$

where: $m = 1.268$

$b = -0.024$

ΔP_o = pressure drop across orifice, inches of water

T_a = ambient temperature, Kelvin

P_a = ambient pressure, mm Hg

The flow rate through the orifice corrected to standard conditions (Q_{std}),
in cubic meters per minute, is:

$$Q_{std} = \frac{\left[\left(\sqrt{\Delta P_o \left(\frac{P_a}{T_a} \right) \left(\frac{298}{760} \right)} \right) - b \right]}{m} \quad r = 0.9998$$

where: $m = 2.025$

$b = -0.033$

ΔP_o = pressure drop across orifice, inches of water

T_a = ambient temperature, Kelvin

P_a = ambient pressure, mm Hg

SH

Reviewed

3/25/2009

Date



**ORIFICE TRANSFER STANDARD CALIBRATION
QUALITY ASSURANCE**

Orifice Transfer Standard# B

The following table is a comparison of measured flow rate versus the flow rate calculated from the new calibration equation. Quality Assurance guidelines require the difference at each point to be less than 2% for a valid calibration. A minimum of three measurement points are required within the operational flow rate interval (1.019 to 1.246 m³/min for PM10 samplers and 1.1 to 1.7 m³/min for TSP samplers).

Q _a measured	Q _a calculated	difference
0.919	0.914	-0.58%
1.046	1.053	0.61%
1.133	1.131	-0.13%
1.218	1.222	0.38%
1.313	1.312	-0.07%
1.374	1.371	-0.23%
1.447	1.447	-0.01%

References: 40 CFR 50, Appendix B, Reference Method for the Determination of Suspended Particulate Matter in the Atmosphere (High Volume Method); 40 CFR 50, Appendix J, Reference Method for the Determination of Particulate Matter as PM10 in the Atmosphere; and Quality Assurance Handbook for Air Pollution Measurement Systems: Volume II. Ambient Air Specific Methods, (EPA 600/4-77/027a, June 1992), Sections 2.2.2.5 and 2.11.2.2.1.

Data Input

Roots Meter SN:	629846					
DATE:	3-Mar-09					
ORIFICE #:	B					
TECH:	Cory Medill					
TEMP (°C):	23.70					
PRES("Hg):	25.83					
CLIENT:	IML Air Science					
LOCATION:	Sheridan, WY					
		POINT	DELTA VOLUME m ³	TIME MIN	DELTA H roots mmHg	DELTA H orifice "H ₂ O
		1	3.3985	3.6713	4.3902	2.8500
		2	3.3985	3.2192	5.8847	3.8000
		3	3.3985	2.9692	6.8188	4.4000
		4	3.3985	2.7567	8.0331	5.1500
		5	3.3985	2.5508	9.3409	5.9500
		6	3.3985	2.4348	10.1815	6.5000
		7	3.3985	2.3078	11.3958	7.2500

POINT	Actual Flow			POINT	Standard Flow		
	V _a m ³	Q _a m ³ /min	Y-AXIS		V _{std} m ³	Q _{std} m ³ /min	Y-AXIS
1	3.376	0.919	1.136	1	2.925	0.797	1.572
2	3.368	1.046	1.311	2	2.919	0.907	1.815
3	3.363	1.133	1.411	3	2.915	0.982	1.953
4	3.357	1.218	1.526	4	2.909	1.055	2.113
5	3.350	1.313	1.641	5	2.903	1.138	2.271
6	3.346	1.374	1.715	6	2.899	1.191	2.373
7	3.339	1.447	1.811	7	2.894	1.254	2.507

Certificate of Accuracy

Transfer Standard Type: Electronic Manometer Certificate No: M 050309. 04

Transfer standard, model: Dwyer Series 475-1 Mark III Digital Manometer

Serial number: IML 0983

submitted by/owner: Inter-Mountain Laboratories, Inc.

Air Science Division

555 Absaraka Street

Sheridan, WY 82801

Was compared to Chinook Engineering Streamline Pro Multi Cal System Serial Number BENCH 1. BENCH 1 is traceable through Meriam Instrument Reference Manometers:

Model number: 30EBX25TM Ser. No.: 131760-M1 Scale number: SC-4208-12

Model number: 30EBX25TM Ser. No.: 158411-S1 Scale number: SC-4208-17

Certified accuracy of ± 0.02 "H₂O

Scale is NIST Traceable to Optical Comparator, SN E37618, and Gage Rod, SN 3388A

Date: 05/03/09 Lab temperature: 69.7 °F
 Lab pressure: 657.1 mm Hg

Reference Manometer ("H ₂ O)	Transfer Standard ("H ₂ O)	Difference from Reference ("H ₂ O)	Transfer Standard Correction* ("H ₂ O)
0.50	0.50	0.00	0.00
2.00	1.98	-0.02	0.02
5.00	4.97	-0.03	0.03
10.00	9.97	-0.03	0.03
19.50	19.50	0.00	0.00

Note:

If no sign is given on the correction, the true pressure is higher than the indicated pressure. If the sign is negative, the true pressure is lower than the indicated pressure.

Transfer Standard adjustments made? YES NO

Post-calibration measurements:

Reference Manometer ("H ₂ O)	Transfer Standard ("H ₂ O)	Difference from Reference ("H ₂ O)	Transfer Standard Correction* ("H ₂ O)

Reviewed: _____



Date: May 3, 2009

Roger L. Sanders, PE

Chinook Engineering

a division of Inter-Mountain Laboratories, Inc.

555 Absaraka Street

Sheridan, Wyoming 82801 USA

(307) 672-7790

chinook@imlinc.com



CERTIFICATE OF CALIBRATION

Test Unit

Model: 18802
 Motor SN: CA03156
 Control Unit SN: IML 0857
 Range: 200-15000 RPM

Motor RPM	Indicated RPM					
	Clockwise Output Range			Counter Clockwise Output Range		
	Low	High	Average	Low	High	Average
600	600.0	600.1	600.0	600.0	600.1	600.0
1200	1199.9	1200.1	1200.0	1199.9	1200.1	1199.9
2400	2399.8	2400.3	2399.9	2399.8	2399.8	2399.8
4200	4199.7	4200.6	4199.9	4199.7	4200.6	4199.8
6000	5999.6	6000.6	6000.2	5999.7	6000.6	5999.7
8100	8099.6	8101.2	8100.8	8099.6	8099.6	8099.6
9900	9899.5	9899.5	9899.5	9894.2	9899.5	9898.0

The instrument above has been presented for inspection and test as shown
 The indicated work was performed using standards traceable to the National Institute of Standards and Technologies (NIST)

Standard SN: 51892014
 Technician: C. Medill
 Date: 1/5/2009

THE BRUNTON COMPANY

Certificate Of Calibration

Equipment Owner:

Name: Inter-Mountain Labs (IML 0942)

Address: 555 Absaroka

City, State, Zip: Sheridan Wyo 82801

Calibration traceable to the National Institute of Standards and Technology in accordance with Mil-STD-45662A has been accomplished on the instrument listed below by comparison with standards maintained by The Brunton Co. The accuracy and stability of all standards maintained by The Brunton Co. are traceable to national standards maintained by the National Institute of Standards and Technology in Washington, D.C. and Boulder, CO. Complete record of all work performed is maintained by The Brunton Co. and is available for inspection upon request.

This Unit has been calibrated to Lietz TM10E serial number 30937 traceable to N.B.S. no. 738 227675 this 27 Day of February 20 09

DESCRIPTION: Pocket transit

PURCHASE ORDER: 186512

ORDER NUMBER: 2047421

LOT NUMBER: 1751276

MODEL NUMBER: 5008

SERIAL NUMBER: 5080393535

CALIBRATION DATE: 2-27-09

RECALIBRATION DUE DATE: 2-27-10

Signed: Eddie Purcell
QUALITY CONTROL MANAGER



721 W 1800 N
Logan, UT 84321

Certificate of Calibration

LI-COR PYRANOMETER

MODEL LI-200X

Customer Name : Kristy Kola
Serial Number : PY54289
Calibration Date : 17-Apr-2009
Previous Calibration Date : 12-Aug-2007
Recommended Recalibration Date : 17-Apr-2011
Calibration Factor : **208.60 W m⁻² per mV**
Output : **85.3 μA per 1000 W m⁻²**
Calibration Factor as Received : 198.37 W m⁻² per mV
Output as Received : 89.7 μA per 1000 W m⁻²
Resistor Size (Measured) : 56.2 Ω
Percent Change in Output : -4.91% Percent Change : -2.92%
per Year

- Calibration Procedure
- Calibrated to a heated and ventilated Kipp & Zonen CM21 pyranometer under sunlight for an integrated daily total in Logan, Utah.
 - Calibrated to four LI-COR transfer standard pyranometers under Metal Halide lamps. The transfer standards are calibrated to the Kipp & Zonen CM21.

Traceability The Kipp & Zonen Model CM21 pyranometer is calibrated every two years at NREL in Boulder, CO. NREL reference standards are calibrated every five years to the world meteorological reference in Davos, Switzerland.

Calibration Technician :  Date : Apr 17, 2009