Jesse Martinez
720-317-4269
Platteville, Colorado
Light bollard repair quote for Beebe Draw farms

Work to include :	
Disconnect wires to lights	
Saw cut concrete 2 inches above dirt grade	
Chip concrete down to 2 inches above dirt grade	
Cut rebar and conduit to grade	
Patch top of concrete	
Remount and rewire lights	
Total cost for two bollards	$800.00