Lisa Johnson

From: Craig Ashcroft <coashcroft@msn.com>
Sent: Friday, May 16, 2014 9:46 AM
To: Lisa Johnson
Subject: Revised Costs for "All Metal" Signs

Dear Lisa,
Following are the revised costs for the "Great Rock North" Signs to be fabricated in steel in lieu of wood as per request:

Item 1). (3) ea. 4'-0" x 6'-0" Plywood core, 18ga. sheet metal clad painted signs with backgroud color to match original tank coating color, and with "Great Rock North" logo and address of each facility on each individual sign. Logo to be applied in Original Color Scheme as per request, using urethane finish material.
Signs @ $ 618.00 ea. x (3) units: $ 1,854.00

Item 2). (3) each Steel Post/Framework Sets for Signs, including; 1/4" x 3" x 10'-0" Schedule 40 Pipe Posts, 1/4" x 1" x 1" steel angle iron attachment frames for signs, welded to posts and 1/4" x 4" x 6'-0" steel Plate Top Weather Cap. All Pieces Cut, welded, SP6 "brush blast" cleaned, primed and Finish Coated in standard "white" urethane for visibility.
Post/Frames @ $ 743.00 ea. x (3) units: $ 2,229.00

Install Fee: $ 104.00 ea. x (3) units: $ 312.00

Total Combined cost, all Signs, Post/Frames and Install: $ 4,395.00

Can do Signs only, or Signs plus Post/Frames, with or without installation. Let me know the Districts' decision as soon as is possible.

Thank You,
Respectfully,
C.O. Ashcroft