TLECC
Timber Line Electric & Control Corporation

P.O. Box 793
Morrison CO 80465-0793
303-697-0440
Fax: 303-697-0450
MikeR@tlecc.net

Greatrock North
Jeff Rabas
Jeff Rabas (jeffr@RECinc.net)
SUB: 15212 Power Fail Monitoring and SCADA work

Date 2/7/14

Dear Jeff,

We are pleased to provide this quotation for your review. If an order should result from this quotation, please send us a written purchase order referencing the quotation number and item numbers. If this is your first order with us, please supply us with your credit references and your Dun and Bradstreet number. Please note:

1. All quotations issued, and orders received by **TLECC** are subject to final acceptance by our principal.
2. Shipping dates are based on the best information obtainable from suppliers **AT THE TIME OF QUOTATION**.
3. Quote is valid for 30 days from quote date.

Again, thank you for your inquiry. If we can be of further assistance, please do not hesitate to contact our office.

Sincerely,

Anthony Ortolani

Scope of work:

Provide equipment, installation, and programming for one of two options for power fail monitoring in the Great Rock North Water & Sanitation District.

This is a Not to Exceed T&M quote. The actual billing will reflect time on site and may be less than quoted. The field portion of Option 1 may only take 2 days, a third is added for contingency.

Option #	Description	Price
1	Provide a 480V 3Phase Monitor. • Great Rock – The monitor will need to be installed in an enclosure next to the 480V distribution panel. The power wiring to the monitor will be tapped off of the TVSS breaker. Conduit to the RTU will be ran for the relay signal, and the alarm wired to an available digital input. Programming of the alarm into SCADA. • Rocking Horse Farms – The monitor will be installed in the TVSS bucket next to the breaker. The power wiring will be tapped off of the TVSS breaker. Existing conduit to the RTU will be used if available, or a conduit ran if needed. The signal will be wired to the next available digital input on the RTU. Programming of the alarm into SCADA. • Box Elder - The monitor will be installed in the TVSS bucket next to the breaker. The power wiring will be tapped off of the TVSS breaker. A conduit will need to be ran from the MCC to the RTU as the existing raceways are full. The signal will be wired to the next available digital input on the RTU. Programming of the alarm into SCADA. • This quote includes 3 days of field labor, and one day of programming, 3 phase monitors, a small enclosure for Great Rock North, Travel costs, conduit and raceways, and drafting of CAD prints.	$ 6,490.00
2	Single Phase monitoring from the RTU cabinet. • This option provides power loss from the 120V that feeds the RTU. It will not monitor each phase of the 480V power system, however it will provide notification of a total power loss event occurs. • TLECC will install a single pole relay in each RTU cabinet to be powered constantly. If the power to the RTU drops out the relay will de-energize and the input to the RTU will go away signaling a power event. Programming of alarms into SCADA, drafting of CAD drawings are included. • **This option includes power monitoring at Box Elder, Rocking Horse Farms, Great Rock North, and Both Alluvial Well RTU's.**	$3,820.00

Timber Line Electric and Control Corp. Terms and Conditions of Sale

This quote is valid for 30 days, and is subject to change after that time frame. All quotations issued, and orders received by TLECC are subject to final acceptance by our principal or authorized representative.

Part numbers and shipping dates are based on the best information available at the time of quote and may change. Part numbers change frequently for items such as computers.

Shipping terms: Shipment times are based upon receipt of a written purchase order or contract and signed approval drawings. Unless otherwise noted, all materials are quoted Free On Board point of origin. TLECC's responsibility for loss ceases upon delivery to the carrier. Claims for loss or damage in transit must be made by Buyer against the carrier. If TLECC is delivering to job site, field off loading has not been included in pricing. Additional charges may be assessed for offloading. Buyer, general contractor, or owner shall be responsible for proper storage and handling following shipment.

TLECC's standard terms are Net 30 days with 1% per month late payment charges. These terms apply to materials and service work. Contract job terms are Net 30 days on a work-in-process basis. TLECC reserves the right to change these terms at any time, and has the right to modify the terms for individual customers. All sales are subject to acceptable credit rating of buyer. Any alteration to the terms stated on a TLECC quote will be considered a counter offer and is subject to acceptance in writing by a TLECC authorized representative. Unless clearly stated otherwise, no retainages will be allowed, or payment withheld pending third party payment. In the event of nonpayment, buyer will be subject to finance charges, collection costs and attorney's fees.

Sales, use and excise tax may be required by law. If buyer is tax exempt, buyer shall provide adequate documentation to TLECC. **If buyer is NOT tax exempt, Buyer is responsible for sales and use tax which will be charged on the materials of the job. Please request a sales tax estimate based on the correct sales tax district!**

Any order cancelled after 3 days of acceptance by TLECC may be subject to the cost of special materials, non-resellable goods and completed labor. In any event, TLECC reserves the right to charge the buyer for any and all expenses or labor incurred in connection with a purchase order. TLECC does not offer refunds on customized equipment.

In the event TLECC is unable to ship or deliver parts or perform services pursuant to any purchase order or other contract entered or accepted by TLECC due to a "Fource Majeure" such as an act of God, strike, lockout or other industrial disturbance, act of public enemy, war, blockade, public riot, lightning, fire, flood, explosion, failure to timely receive necessary government approvals, government restraint or any other cause, which is not reasonably within the control of TLECC, TLECC's obligations under the purchase order or other contract shall be suspended during such Force Majeure. If the Force Majeure cannot be promptly removed in TLECC's sole opinion, at TLECC's sole option, the purchase order or other contract may be terminated without further obligation or liability on the part of either party.

TLECC honors a 1 year warranty on new equipment. This includes repair or replacement of said equipment at TLECC's discretion. The equipment warrantee does not include the travel or labor to troubleshoot equipment. TLECC may include the labor at TLECC's discretion. TLECC will honor a 90 day warrantee on all installation labor. Except for those expressly provided for herein, no other warrantee express or implied applies. TLECC is not liable for lightning damage, vandalism, or acts of God. Warrantee will be void on equipment which has been serviced by persons other than TLECC employees.

Limitations of liability: TLECC is not responsible for any modification or repairs to TLECC products made by persons other than TLECC personal. Timber Line is not liable for any and all consequential and incidental damages arising out of, or in connection with any purchase order or contract for equipment or services. This includes but is not limited to installation, service, or product's failure to perform, in connection with purchase order, contract, or verbal request for service.